

1 060903

Plugged 11-17-86

15-119-10164-0000

API NUMBER 15-119-20,745

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW, SEC. 18, T 33 S, R 30 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4752

Lease Name Langhofer Well # 1

Operator: Source Petroleum  
Name & Address: 910 Century Plaza Bldg.  
111 West Douglas  
Wichita, KS 67202

County Meade 199.23  
Well Total Depth 6130 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1550

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling Inc. License Number 5382

Address W. Hwy 50, Box 916, Garden City 67846

Company to plug at: Hour: 4:45 p.m. Day: 17 Month: 11 Year: 19 86

Plugging proposal received from Roger Pierson

(company name) Cheyenne Drilling Inc. (phone) 316-277-2062

were: 5 1/2" at 6128' Perfs at 5881-87'

1st plug set CIBP at 5830' and dump 2 sx cement.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 p.m. Day: 17 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug set Cast Iron Bridge Plug at 5830' and dump 2 sx cement.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
release 8 5/8" wiper plug and pump 150 sx cement.

Maximum pressure 700 psi and shut in 200 psi.

NOV 24 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2842' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(do not check) observe this plugging.

DATE 11-24-86

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 15423  
11-11

JAN 08 1987