

1051976

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 175-21,462-0000  
C SW SW, SEC. 10, T 33 S, R 32 W/EX  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263  
Operator: Midwestern Exploration Co.  
Name & Address: P.O. Box 1884  
Liberal, KS 67905-1884

Lease Name Chambers Well # 3-10  
County Seward 102.25  
Well Total Depth 3146 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 585

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151  
Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: \_\_\_\_\_ Day: 1 Month: 11 Year: 1995

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

- Work: 4 1/2" at 3150' with 125 sx cement, PBD 2665', Perfs at 2676-88, 2596-2606, 2626-34'.  
1st plug pump 20 sx cement and 2 sx hulls on bottom,  
2nd plug at 1490' with 50 sx cement,  
3rd plug at 610' with 50 sx cement,  
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 6 p.m. Day: 1 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 2 sx hulls over perfs,  
2nd plug pulled to 1490' and spotted 50 sx cement,  
3rd plug pulled to 1231'. Pipe stuck. Shot pipe at 1021', pulled to 610' and spotted 50 sx  
cement.  
4th plug pulled to 40' and pumped 10 sx cement.

STATE CORPORATION COMMISSION  
NOV 7 1995

Remarks: Used common cement by Sargent & Horton. Recovered 2323' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (copy) did not observe this plugging.

DATE 11-16-95  
INV. NO. 44046

Signed Richard M. Lacey  
(TECHNICIAN)