

1060249

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,585-0000

20 NW-11W, SEC. 24; T 33 S, R 32 W

660 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6979

Lease Name Engrim Well # 1 24

Operator: Funk Exploration

County Seward

Name & Address 210 West Park Ave. # 1000

Well Total Depth 6291 204.46 feet

Oklahoma City, OK 73102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1491

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sam's Well Service License Number 6145

Address Guymon, OK

Company to plug at: Hour: 7:00 am Day: 19 Month: June Year: 19 84

Plugging proposal received from Bob Mitchell

(company name) Funk Exploration (phone) 405-235-2640

were: 4 1/2 set at 6288' PBD 6231' Perfs 5754-5824'

1st plug set a CBP at 5739 and 2 sx cement

2nd plug at 1540' with 50 sx cement

3rd plug at 760' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:58 am Day: 19 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 6288' PBD 6231' Perfs 5754-5824'

1st plug set a CBP at 5739' with 2 sx cement, 2nd plug at 1540' with 50 sx cement,

3rd plug at 760' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at

40' -- cement to surface with 10 sx cement.

Remarks: Used Class H cement by Halliburton. They recovered 3050' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (name) did not observe this plugging.

DATE 7-3-84

Signed Paul A. Luthin
(TECHNICIAN)

WV. NO. 2256 JUL 24 1984 AUG 16 1984
6-19 2-2