

1 080370

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C NW SE \_\_\_\_\_, SEC. 22 \_\_\_\_\_, T 33 S, R 32 W/R  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,849-0000

1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8758  
Operator: Raw Energy Corporation of Kansas  
Name & Address 7200 West 13th, Suite 8  
Wichita, KS 67212

Lease Name Arkalon Well # 2-22  
County Seward 201.50  
Well Total Depth 6200 (lower Chester) feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1431

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J. B. Bohannan Drilling, Inc. License Number 5879  
Address Box 6, Liberal, KS 67901

Company to plug at: Hour: 6:00 pm Day: 3 Month: May Year: 19 85

Plugging proposal received from Jay Bohannan  
(company name) Bohannan (phone) 316-624-2202

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 3300' with 100 sx cement
- 2nd plug at 1480' with 50 sx cement
- 3rd plug at 700' with 40 sx cement  
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. A. Muz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00 pm Day: 3 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3300' with 100 sx cement, 2nd plug at 1480' with 50 sx cement, 3rd plug at 700' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
(if additional description is necessary, use BACK of this report)

~~operator~~ (did not) observe this plugging.

Signed J. A. Muz  
(TECHNICIAN)

INVOICED  
DATE 5-14-85  
INV. NO. 8138  
5-3

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: April 15 1985  
month day year

API Number 15- 175-20,849

OPERATOR: License # 8758  
Name RAW Energy Corporation of Kansas  
Address 7200 West 13th Suite 8  
City/State/Zip Wichita, Kansas 67212  
Contact Person Benny Green  
Phone (316)722-6382

A C NW SE Sec 22 Twp 33 S, Rge 32  East  West  
(location)  
1980 Ft North from Southeast Corner of Section  
1980 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5879  
Name J. B. Bohannon Drilling, Inc.  
City/State Liberal, Kansas

Nearest lease or unit boundary line 1980 feet  
County Seward  
Lease Name Arkalon Well# 2-22

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

If OWWO: old well info as follows:

Depth to Bottom of fresh water 520 feet  
Lowest usable water formation Top of Permian  
Depth to Bottom of usable water 625 feet

Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 6000 feet  
Projected Formation at TD Chester  
Expected Producing Formations MORROW

Surface pipe by Alternate: 1  2   
Surface pipe to be set 1500 feet  
Conductor pipe if any required 40 feet  
Ground surface elevation 2637 feet MSI  
This Authorization Expires 9-28-85  
Approved By 3-28-85 *RC*

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 03/27/85 Signature of Operator or Agent

*Benny Green* Title District Manager  
Benny Green

MHC/MOHE 3-28-85 Form C-1 4/84

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1985  
CONSERVATION DIVISION  
Wichita, Kansas