

1090240

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,051-00-00

C SW SW , SEC. 16 , T 28 S, R 11 W/R
660 feet from ~~XXX~~ SE Corner of section line
4620 feet from ~~XXX~~ W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5219

Lease Name Bortz Well # 1

Operator: Kimbark Oil & Gas Company

County Pratt

Name & Address 1580 Lincoln Street, Suite 700

Well Total Depth 3800 123.50 feet

Denver, CO 80203

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 443

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Arapaho Well Service License Number 5476 Under DNB

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 2:00 pm Day: 19 Month: October Year: 19 84

Plugging proposal received from Raymond Eaves

(company name) Arapaho (phone) 316-687-5471 Under DNB

were: 5 1/2" set at 3816' PBDT 3760 Perfs at 3705-14

Squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 80 sx cement.

Plugging Proposal Received by R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:30 pm Day: 19 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3816' PBDT 3760' Perfs at 3705-14'

Squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 80 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1984
10-24-84
CONSERVATION DIVISION
WICHITA, Kansas

Remarks: No recovery

(If additional description is necessary, use BACK of this form.)

INVOICED (date) observe this plugging.

Signed R. Barluttan
(TECHNICIAN)

DATE 10-29-84

INV. NO. 4509 10-19

NOV 19 1984