

2-14

TO: 1 040226

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,911-40-00
NE SW SW SEC. 16, T 28 S, R 11 W/E
780 feet from S section line
4500 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3701

Lease Name Bortz-Yates Well # 1-16

Operator: Balcron Oil Company

County Pratt 121.88

Name & Address P.O. Box 21017

Well Total Depth 3750 feet

Billings, MT 59104

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347
Chase, KS 67524

Company to plug at: Hour: 2:15 p.m. Day: 14 Month: 2 Year: 1989

Plugging proposal received from Frank Clark

(company name) Balcron Oil Company (phone) 316-582-2546

were: 4 1/2" at 3749' PBTB 3724' Perfs at 3699-3704'

1st plug sand back to 3640' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 14 Month: 2 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 3640' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, and 120 sx cement.

Maximum pressure 1200 psi and shut in 900 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3040' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
(Do not XXXXXX) observe this plugging.

DATE 2-14-89

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 23954
2-14

RECEIVED

STATE CORPORATION COMMISSION

FEB 16 1989
02-11-89

CONSERVATION DIVISION
Wichita, Kansas

5070