

To: 1 020458  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-24

API NUMBER 15- 175-01,006-0002- 263  
C NW SE, SEC. 4, T. 33 S, R. 33 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447  
Operator: OXY USA INC.  
Name & Address: P.O. Box 26100  
Oklahoma City, OK 73126-0100

1980 feet from S section line  
1980 feet from E section line  
Lease Name Beck B Well # 2  
County Seward  
Well Total Depth 6353 206.47 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1584

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor OXY USA INC. License Number 5447  
Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 12:30 p.m. Day: 24 Month: 4 Year: 1992

Plugging proposal received from Charles Glasscock  
(company name) OXY USA INC. (phone) 316-675-2293

were: 5 1/2" at 6066' w/400 sx cement, CIBP 2725', Perfs at 2542-2664'  
1st plug set CIBP at 2500' w/2 sx on top, w/2 sx on top  
2nd plug run tubing to 1610' and pump 50 sx cement,  
3rd plug pump 50 sx cement at 750',  
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 p.m. Day: 24 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2500' with 2 sx cement on top,  
2nd plug loaded hole with mud and ran tubing to 1610', pumped 50 sx cement, displaced w/mud,  
3rd plug pumped 50 sx cement at 700', displaced with mud,  
4th plug pumped 10 sx cement at 60-0'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery, 5 1/2" cemented to surface.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (did, ~~did not~~) observe this plugging.

DATE 5-15-92

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 35247

STATE CORPORATION COMMISSION  
RECEIVED  
MAY 1 1992  
CONSERVATION DIVISION  
Wichita, Kansas