

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,689-0000

NE-SW/4 Sec. 7, T 33 S, R 33 W/4

1980 feet from ~~SW~~/S section line

1980 feet from W/~~SW~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263

Lease Name Fitzgerald Well # 1-7

Operator: Jack Reere d/b/a
Name & Address Midwestern Exploration
P.O. Box 1869
Liberals, Kans 67901

County Seward

Well Total Depth 6400 feet 208'

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1610

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Co License Number 5421

Address 222 Sutton Place Wichita, Kansas 67202

Company, to plug at: Hour: 1:00 AM Day: 19 Month: 6 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Frank Burch

(company name) Louery oil field consultant (phone) _____

were: 1st plug @ 1680' w/ 50 sbx cement. 2nd plug @ 640' w/ 35 sbx cement. 3rd plug @ 40' to 0' w/ 10 sbx cement on solid bridge. Circulate 15 sbx cement in rat hole & 10 sbx cement in mouse hole. Farmer wants water well, they have been advised to get released. The plugging accomplished by Halliburton Co.

Signed Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 Day: 19 Month: 6 Year: 1983

ACTUAL PLUGGING REPORT This hole was plugged as orders given.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1983

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cement used w/ 60/40 pebbles 2 3/4 gal & 3% C.C.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 6-24-83
INV. NO. 4683-W

Signed Paul A. Luthie
(TECHNICIAN)