

1060510

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,782 - 0000

SW NE _____, SEC. 7, T 33 S, R 33 (W) X

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263

Lease Name Strickland Well # 1-7

Operator: Midwestern Exploration Co.

County Seward 207.35

Name & Address 111 East 11th

Well Total Depth 6380 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1630 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 2:00 pm Day: 13 Month: March Year: 19 85

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6379' PBD 6112' Perfs at 6082-6092' and 4182-86'

Spot plugs through 4 1/2" with mud between plugs (last 2 plugs)
1st plug pump 20 sx cement to bottom (spot through tubing)

2nd plug at 4200' with 20 sx cement (spot through tubing)

3rd plug at 2850' with 75 sx cement

4th plug at 1630' with 35 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4:00 pm Day: 13 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement to bottom, 2nd plug at 4200' with
20 sx cement, 3rd plug at 2850' with 75 sx cement, 4th plug at 1630' with 35 sx cement

5th and 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10
sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1985

Remarks: Used common sacked cement by Sargent's. Recovered 25' casing.
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(old ~~copy~~) observe this plugging.

DATE 3-26-85

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 7445 3-13