

1031505

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-21,744-0000
SW NE SW SW SEC. 9, T 33 S, R 33 W

8-17

CONSERVATION DIVISION - PLUGGING SECTION 860 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 860 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HOLIDAY "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 204.75

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 6300 FEET

OPERATOR: ANADARKO PETROLEUM CORP

PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 351

SURFACE CASING: SIZE 8 5/8" FEET 1597'

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CHEYENNE DRILLING LICENSE NUMBER 5382

ADDRESS PO BOX 916, GARDEN CITY, KS 67846

COMPANY TO PLUG AT: HOUR: 4:00 AM DAY: 17 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM IKE

(COMPANY NAME) CHEYENNE DRILLING (PHONE) 316-277-2062

WERE:

1ST PLUG AT 3200' WITH 100 SX CEMENT, 2ND PLUG AT 1620' WITH 50 SX CEMENT,

3RD PLUG AT 600' WITH 25 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:30 AM DAY: 17 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 3200' WITH 100 SX CEMENT, 2ND PLUG AT 1620' WITH 50 SX CEMENT,

3RD PLUG AT 600' WITH 25 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Steve Durrant (TECHNICIAN) FORM CP-2/3

INVOICED

DATE 8-20-98

INV. NO. 51180

RECEIVED
KANSAS CORPORATION
1998 AUG 20 9:54