

To: 090429
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-27

API NUMBER 15- 175-21,397-0000

NW SE NW, SEC. 14, T 7 S, R 31 XX
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Headrick Well # 1-14

Operator: Landmark Oil Exploration, Inc.

County Seward

Name & Address 250 N. Water, Ste. 308

Well Total Depth 5738 186.48 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1559

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co., Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 27 Month: 5 Year: 19 94

Plugging proposal received from Bill Wynn

(company name) Murfin Drilling Co., Inc. (phone) 316-267-3241

Remarks: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1560'

1st plug at 1580' with 50 sx cement, 2nd plug at 600' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:15 a.m. Day: 27 Month: 5 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1580' with 50 sx cement,

2nd plug at 600' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 02 1994

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-7-94

INV. NO. 40541

5-27

Signed [Signature]
(TECHNICIAN)

EFFECTIVE DATE: 5-9-94

State of Kansas

15-175-21,397-0000

FORM MUST BE SIGNED

DISTRICT # 1
SEA7... Yes... No

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date May 4 1994
month day year

Spot NW SE NW Sec 14 T33S S. Rg R31W East West

OPERATOR: License # 06113
Name: Landmark Oil Exploration, Inc.
Address: 250 N. Water, Suite 308
City/State/Zip: Wichita, KS 67202
Contact Person: Jeff Wood
Phone: (316) 265-8181

3630 feet from South / North line of Section
3630 feet from East / West line of Section
IS SECTION XX REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Seward
Lease Name: Headrick Well #: #1-14
Field Name: unnamed

Is this a Prorated/Spaced Field? yes XX no

Target Formation(s): Morrow

Nearest lease or unit boundary: 990'

Ground Surface Elevation: 2749' feet MSL

Water well within one-quarter mile: yes XX no

Public water supply well within one mile: yes XX no

Depth to bottom of fresh water: 450'

Depth to bottom of usable water: 500'

Surface Pipe by Alternate: 1 XX 2

Length of Surface Pipe Planned to be set: (1550) 500

Length of Conductor pipe required: N/A

Projected Total Depth: 5700'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:
... well ... farm pond XX other

DWR Permit #: ...

Will Cores Be Taken? yes XX no

If yes, proposed zone: ...

CONTRACTOR: License #: 30606
Name: Murfin Drilling Co., Inc.

316 267 324

Well Drilled For: Well Class: Type Equipment:

- XX Oil ... Enh Rec ... Infield XX Mud Rotary
- XX Gas ... Storage ... Pool Ext. ... Air Rotary
- ... OUVO ... Disposal XX Wildcat ... Cable
- ... Seismic; ... # of Holes ... Other
- ... Other

If OUVO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth

Directional, Deviated or Horizontal wellbore? yes XX no
If yes, true vertical depth: ...
Bottom Hole Location: ...

Exp. 11/4/94

AFFIDAVIT

500' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Sell Wynne
SPUD DATE 5-11-94 INIT. mw

LENGTH SURFACE PLANNED 1550

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2 @ 1559 CONDUCTOR
ANHYDRITE T- B- 1560 ELEVATION

TD 5738 FORMATION MISS

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ 100 SX

Anhydrite Base @ Ft. W/ SX

1/2 Base Anyh. @ 600 Ft. W/ 50 SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 1580 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL Landmark (Irr. Well) Wichita, Kansas

TECHNICIAN SM DATE 5/22/94

TYPE OF CEMENT 62/40 670

STARTING TIME 1:30 (AM/PM) DATE 5-27-94

COMPLETION TIME 4:15 (AM/PM) DATE 5-27-94

CEMENT COMPANY Halliburton

STATE OF KANSAS RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
DATE 5-22-1994
DATE 5-27-94