

To: 1 020862 5-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,108-0001
C SW NW, SEC. 2, T 33 S, R 31 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Traylor A Well # 2
County Seward 196.95
Well Total Depth 6060 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1604

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 16 Month: 5 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 6059' w/100 sx cement, PBSD 5600', Perfs at 5555-5558'

1st plug set CIBP at 5600',

2nd plug pump 30 sx cement at perfs with tubing, 3rd plug pump 25 sx cement at 2730',

4th plug pump 50 sx cement at 1635', 5th plug pump 40 sx cement at 700',

6th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 p.m. Day: 16 Month: 5 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug CIBP set at 5600',

2nd plug pumped 30 sx cement at perfs with tubing,

3rd plug pumped 25 sx cement at 2730',

4th plug pumped 50 sx cement at 1635',

5th plug pumped 40 sx cement at 700',

6th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent & Horton. Recovered 2730' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(do not check) observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)

DATE 6-12

WELL NO. 42942