

To: 1 100070
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 175-21,342-0001
E/2 NW SW, SEC. 5, T. 33 S, R. 31 WXX
1980 feet from S section line
4290 feet from E section line

10-10
TECHNICIAN'S PLUGGING REPORT

Operator License # 6120
Operator: Cabot Oil & Gas Corporation
Name:
Address: 9400 N. Broadway, Ste. 608
Oklahoma City, OK 73114

Lease Name Massoni Well # 3-5
County Seward 198.25
Well Total Depth 6100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1512

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 9 Month: 10 Year: 1996

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

were: 5 1/2" at 6100' w/270 sx cement, PBDT 3260', Perfs at 3072-3176'
CIBP set at 4560' and at 3260' with 2 sx cement on top.

1st plug pump 2 sx hulls with 25 sx cement, displace from 3072-2872',
2nd plug pump 50 sx cement and displace to 1540',
3rd plug pump 50 sx cement and displace to 550', 4th plug pump 10 sx cement from 40-0'.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2 p.m. Day: 10 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT CIBP set at 4560' and 3260' with 2 sx cement on top,
1st plug pumped 2 sx hulls mixed with 25 sx cement, displaced from 3072-2872',
2nd plug pumped 50 sx cement, displaced to 1540',
3rd plug pumped 50 sx cement, displaced to 550',
4th plug pumped 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 2556' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE OCT 17 1996
INV. NO. 46699
10-10

Signed Gary Winters
(TECHNICIAN)

RECEIVED
KANSAS CORP COM
1996 OCT 15 P 12:19