

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Finney State Office Building
130 South Market
Wichita, Kansas 67202

15-175-21420-0000

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-21420-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE SALLEY "K" WELL# 1H SEC. 33 T. 33S R. 33 (XXXX/West)

NE - NE - SW - SW SPOT LOCATION/QQQQ COUNTY SEWARD

1250 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 674' CEMENTED WITH 390 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 2595' CEMENTED WITH 310 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: SLOTTED LINER 2557-2680'

ELEVATION 2835 / --- T.D. 2680' PBTD 2680' ANHYDRITE DEPTH BASE @ 1598'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING: NOTIFY KCC IN DODGE CITY AT LEAST 5 DAYS PRIOR TO PLUGGING OPERATIONS @ (316) 225-6760. MIRUPU. TIH W/1-1/2" TBG TO 2600'. CIRC HOLE W/9 PPG MUD. SPOT 2 SX HULLS & 10 SX CLASS H CMT FROM 2600-2550'. DISPL W/MUD. TOH TO 724'. SPOT 5 SX CLASS H CEMENT FROM 724-624'. DISPL W/MUD. TOH TO 40'. SPOT 5 SX CLASS H CMT FROM 40-3'. CUT OFF 8-5/8 & 5-1/2" CSG 3' BELOW GL AND CAP. PERMANENTLY INSCRIBE THE DATE OF PLUGGING AND WELL NAME ON TOP OF CAP. RDMOPU & RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? FILED WITH ORIGINAL ACO-1 (4/95)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JERRY RUTTMAN PHONE# (316) 624-6253

ADDRESS P.O. BOX 351 City/State LIBERAL, KANSAS 67905-0351

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-1-96 AUTHORIZED OPERATOR/AGENT: J. L. Ashton
J. L. ASHTON (signature) DIV. PROD. MGR.

8/96

RECEIVED
KANSAS CORP COM
1996 FEB -5 A 11:15

1/96

D



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 6, 1996

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Salley "K" #1H
API 15-175-21,420
1250 FSL 1250 FWL
Sec. 33-33S-33W
Seward County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

ANADARKO PETROLEUM CORPORATION

PHONE 316 - 624 - 6253 1701 NORTH KANSAS AVE.

RECEIVED
KANSAS CORP COMM
LIBERAL, KANSAS 67905 - 0351
P.O. BOX 351

1996 FEB -5 A 11:07

Anadarko 

February 1, 1996

**Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, RM 2078
Wichita, Kansas 67202**

**Re: Salley "K" No. 1H
Section 33-33S-33W
Seward County, Kansas**

Gentlemen:

Attached is Form CP-1 (Well Plugging Application Form) for the above referenced well.

If you have any questions, please advise.

Very truly yours,

L. Marc Harvey

**L. Marc Harvey
Drilling Technical Assistant
LMH/sh**

Enclosures

**cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
WI Owners**

sallyk1h.wp6