

15-119-00154-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 7/2/53 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR BEREXCO INC. OPERATOR'S LICENSE NO. 05363

ADDRESS 970 Fourth Financial Ctr., Wichita, KS 67202 PHONE # (316) 265-3311

LEASE (FARM) Armentrout WELL NO. A #1 WELL LOCATION SW NE COUNTY Meade

SEC. 16 TWP. 33S RGE. 30 (or (W) TOTAL DEPTH 5910 PLUG BACK TD 5742

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 13 3/8 SET AT 635' CEMENTED WITH 500 SACKS

Intermediate Casing Size 9 5/8 2670' 800

Production CASING SIZE 5 1/2 SET AT 5830' CEMENTED WITH 400 SACKS

PERFORATED AT 5758-62, 5721-31, 4572-76 (squeezed off)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 4530', cut off 5 1/2" casing @ ±3100',

spot 50 sx cmt @ 1670', 40 sx @ 650', 10 sx @ 40'

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? attached ^{log}
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12/2/90 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bob Sargent PHONE # (316) 624-7455

ADDRESS 620 S. Lincoln, P.O. Box 506, Liberal, KS 67901

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, P.O. Box 506, Liberal, KS 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Evon C May
(Operator or Agent)

DATE: 11/15/90

①

SCHUMBERGER WELL DRILLING CO.



ELECTRICAL
LATERALS-3"
MICROL

COUNTY: MEADE
FIELD or WILDCAT
LOCATION SEC. 16-33S-30W
WELL ARMENTROUT #1
COMPANY COLUMBIAN FUEL CORP.

COMPANY COLUMBIAN FUEL CORPORATION
WELL ARMENTROUT #1
K. G. S. LUBA
FIELD WILDCAT
LOCATION SEC. 16-33S-30W
COUNTY MEADE
STATE KANSAS
Property of Kansas Geological Survey
540 Petroleum Bldg
Wichita, Kansas

RUN No.	ONE L.L.	ONE G.R.	TWO E.S.
Date	6-5-53	6-5-53	7-2-53
First Reading	2674	2676	5912
Last Reading	633	633	2672
Feet Measured	2041	2043	3240
Csg. Schlum.	633	- - -	2672
Csg. Driller	635	-635	2670
Depth Reached	2677	2677	5913
Bottom Driller	2675	2675	5910
Depth Datum	R.B. OR 9.5' ABOVE G.L.		
Mud Nat.	7EOGEL	7EOGEL	AOUAGEL
" Density	10.5	10.5	9.65
" Viscosity	37	37	42
" Resist.	.072@70 °F	.072@70 °F	1.50@94F
" Res. BHT	.055@90 °F	.055@90 °F	1.3 @122F
" pH	7 @ °F	7 @ °F	10.5
" Wtr. Loss	70 CC 30 min.	70 CC 30 min.	12.8cc
Max. Temp. °F	90	90	122
Bit Size IN	12 1/2"	12 1/2"	7 7/8"
Spcas. AM			16"
			64"
			16"
Com. Time	1 HR.	1 1/2 HRS.	1 HR.
Truck No.	1704-LIB	1704-LIB	1700-LIB
Recorded By	STRINGER	STRINGER	HOLLEY
Witness By	BEYACQUA	BEYACQUA	REYNOLDS

RECEIVED
STATE CORPORATION

NOV 19 1950

CONFIDENTIAL
Wichita



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

November 20, 1990

Berexco, Inc.
970 Fourth Financial Ctr.
Wichita, KS 67202

Armentrout A #1
SW NE 16-33-30W
Meade County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b).** Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of David P. Williams in cursive.

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801
(316) 225 - 6760