

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

15-119-20375-0000 CP-1  
FORM CP-1  
Rev. 6/4/84

RECEIVED  
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM  
(File One Copy)

APR 24 1991

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-119-20,375-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR R.J. Patrick Operating OPERATORS LICENSE NO. 6528

ADDRESS Box 1314, Liberal, Ks. PHONE # (316) 624-8483

LEASE (FARM) Burmeister WELL NO. 1 WELL LOCATION NW-SE-SE-SE COUNTY Meade

SEC. 17 TWP. 33 RGE. 30 (E) or (W) TOTAL DEPTH 6056' PLUG BACK TD 5984

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 1520' CEMENTED WITH 750 SACKS

CASING SIZE 4 1/2" SET AT 6056' CEMENTED WITH 400 SACKS

PERFORATED AT 5678' to 84'

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL As required by KCC - Dodge City, Ks.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4-25-1991

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Edgar J. Eves PHONE # (316) 675-8349

ADDRESS Box F, Sublette, Ks. 67877

PLUGGING CONTRACTOR MIDWEST CASING PULLING SERVICE LICENSE NO. 6497

ADDRESS Box F, Sublette, Ks. 67877 PHONE # (316) 675-8349

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Edgar J. Eves  
(Operator or Agent)

DATE: 4-22-91

0

Joan Finney  
Governor

Jim Robinson  
Chairman

Keith R. Henley  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian-J. Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 1, 1991

R. J. Patrick Operating  
Box 1314  
Liberal, KS 67901

Burmeister 1  
API 15-119-20,375  
NE SE SE SE  
Sec. 17-33-30W  
Meade County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

District: #1 304 W. McArtor  
Dodge City 67801  
(316) 225-6760

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

**IMPORTANT**  
 Kans. Geo. Survey request  
 samples on this well.

**KANSAS DRILLERS LOG**

S. 17 T. 33 R. 30 <sup>W</sup>/<sub>W</sub>  
 Loc. 495' FSL & 495' FEL  
 County Meade

API No. 15 — 119 — 20,375  
 County Number

Operator  
Buttonwood Petroleum, Inc.

Address  
320 S. Boston, 2010 Tulsa, Okla 74103


Well No. # 1 Lease Name Burmeister

Footage Location  
 feet from (N) (S) line 495' FSL feet from (E) (W) line 495' FEL

Principal Contractor DaMac Drilling Geologist Sentry Mud Logging

Spud Date 12-18-79 Total Depth 6056' P.B.T.D. 5984'

Date Completed 1-10-80 Oil Purchaser



Elev.: Gr. \_\_\_\_\_  
 DF \_\_\_\_\_ KB \_\_\_\_\_

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"	24#	1520'		600 150	2% CC 3% CC
Production	7 7/8"	4 1/2"	10/5#	6056'	Class H 50/50 Poz	50 150	8% Gel, 12 1/2 Gil 18% Salt, 12 1/2 Gil

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at	Two	5678-84
2 3/8"	5660	5705'		

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
Acidized 500 gals 15% MCA	5678-84'
FRAC'D 14,00- gals gelled 3% Acid with 2% KCL Water	"

**INITIAL PRODUCTION**

Date of first production <u>1-16-80</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>38</u> bbls. MCF <u>5</u> bbls. Gas-oil ratio <u>CFPB</u>
Disposition of gas (vented, used on lease or sold) <u>none</u>	Producing interval (s) <u>5678-84</u>

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Buttonwood Petroleum, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWD, ETC.: 011

Well No. 1 Lease Name Burmeister

S 17 T 33 R 30 E (W)

**WELL LOG**  
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.  
 SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1 (Lansing Limestone) Times= 30"-60"-60'-120" IFP 32-32# - weak blow, 1" ISIP 868# FFP 52-65# - very weak blow FSIP 868# Recovered 100' GCM with SSG	4500	4552	Lansing Marmaton Morrow Shale Upper Mrrw Sd Chester St. Gen	4532 5150 5666 5674 5722 5951
DST#2 (Upper Morrow Sand) Times= 30" - 60" - 60" - 120" IFP 49-8# - Good To Strong Blow, No Gas ISIP 540# FFP 124-131# - Strong Blow, No Gas FSIP 819# Recovered 350' HGCMO	5630	5689		

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 24 1991  
 CONSERVATION DIVISION  
 Wichita Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received \_\_\_\_\_

Signature: *John L. Nicard*  
 Title: Vice President - Exploration  
 Date: April 11, 1980