

15-175-10012-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER NA (of this well) 8/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM) LIGHT "B" WELL NO. 1 WELL LOCATION C SE NW COUNTY Seward

SEC. 32 TWP. 33S RGE. 32 ~~XY~~ (W) TOTAL DEPTH 6144' PLUG BACK TD 6107'

Check One:

OIL WELL GAS WELL X D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 1494' CEMENTED WITH 600 SACKS

CASING SIZE 4 1/2" SET AT 6144' CEMENTED WITH 190 SACKS

PERFORATED AT 5742-5750, 5772-5780 (Morrow)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Rig up Sargents. Pump 1 sx hulls and 50 sxs
cement from 6107-5600'. Shoot csg @ 5000'. Pull csg to 1600'. Spot 100 sxs from 1600-1400'.

Pull out csg. Pump 10 sxs from 40' to 0'. Cut off and cap 8 5/8" csg below ground level. Rig
(If additional space is needed use back of form) down Sargents.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? Drillers Log
(If not, explain) attached

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6/88

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-1455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)
M. L. Pease, Division Production Manager

AUG 14 1987 DATE: 8/12/87



Mike Hayden Governor
Keith R. Henley Chairman
Rich Kowalewski Commissioner
Margalee Wright Commissioner
Judith A. McConnell Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

NOV 14 '87

EXPIRES

August 14, 1987

WELL PLUGGING NOTICE

Light "B" #1
C SE NW
Sec. 32-33S-32W
Seward County

Anadarko Petroleum
P. O. Box 351
Liberal, KS 67901

Gentlemen;

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760