

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

129

API # 15-189-21,410-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS 3017 N. Cypress CITY Wichita

STATE Kansas ZIP CODE 67226-4003 CONTACT PHONE # (316) 636-2737

LEASE Morgan "M" WELL# 1-6 SEC. 6 T. 33S R. 39 (East/West)

- C - SW - SE SPOT LOCATION/QQQQ COUNTY Morton

660' FEET (in exact footage) FROM (S/W) (circle one) LINE OF SECTION (NOT Lease Line)

1980' FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1718' CEMENTED WITH 510 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3252/3265 T.D. 6284 PBSD _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug and abandon using 60/40 Poz, 6% gel. Set 1st plug

3400' w/100 sx; 2nd plug set @ 1710' w/50 sx; 3rd plug set @ 600' w/25sx; 4th plug

set @ 40' w/10 sx. 15 sx in rathole and 10 sx in mousehole.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH KVS.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# (316) 272-1296

ADDRESS P. O. Box 2250 city/state Garden City, KS 67846

PLUGGING CONTRACTOR Sweetman Drilling, Inc. KCC LICENSE # 5658
(company name) (contractor's)

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003 PHONE # (316) 634-6151

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-07-95 AUTHORIZED OPERATOR/AGENT: _____

(signature)