

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21767-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 25-16S-20W
536 feet from S Section Line, 1587 feet from E Section Line
Lease Name: WALKER Well #: 1
County: RUSH Total Vertical Depth: 3900 feet

Operator License No.: 34134
Op Name: TREK RESOURCES, INC.
Address: 4925 GREENVILLE AVE., STE 915
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		WITH 2 SX CMT
PROD	5.5	3900	0	WITH 300 SX CMT
SURF	8.625	208		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2014 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: JEFF PFANNENSTIEL Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. LOAD HOLE & RUN A BOND LOG. IF NO CMT BEHIND PIPE AT PERMIAN THEN PERFORATE AND RUN TBG & CIRCULATE CMT TO SURFACE. THEN TIE ONTO CASING AND PUMP 80 SX CMT OUT PERFS. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2014 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3800' WITH 2 SX CMT. LOAD HOLE & RUN BOND LOG. DIDN'T SEE ANY CMT AT PERMIAN. SHOT HOLES AT 730'. RUN TBG TO 775' & PUMPED 80 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TIED ONTO CASING AND PUMPED 75 SX CMT & 200# HULLS. MAXIMUM PRESSURE 1100#. TIED ONTO BACKSIDE & PUMPED 1/8 BBL. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
3847	3850		

Remarks: USED 60/40 POZMIZ 4% GEL BY CONSOLIDATED.

Plugged through: CSG

1/14/15 CKM

District: 01

RECEIVED
JAN - 6 2015
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)

KCC WICHITA
JAN 08 2015
RECEIVED

[Handwritten signature]