

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-21773-00-00  
Spot: NWSWNWNW Sec/Twnshp/Rge: 27-16S-20W  
808 feet from N Section Line, 140 feet from W Section Line  
Lease Name: KIRSTEN Well #: 1  
County: RUSH Total Vertical Depth: 4039 feet

Operator License No.: 34134  
Op Name: TREK RESOURCES, INC.  
Address: 4925 GREENVILLE AVE., STE 915  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		WITH 2 SX CMT
PROD	4.5	4039	0	WITH 350 SX CMT
SURF	8.625	209		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2014 9:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JEFF PFANNENSTIEL Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. LOAD HOLE & RUN BOND LOG TO SEE WHERE CMT IS. IF NO CMT BEHIND PIPE AT PERMIAN THEN PERFORATE AND RUN TBG & CIRCULATE CMT TO SURFACE. TIE ONTO CASING AND PUMP 80 SX CMT OUT PERFS. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/29/2014 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3850' WITH 2 SX CMT. LOAD HOLE & RUN BOND LOG. DIDN'T SEE ANY CMT AT PERMIAN. SHOT HOLES AT 740'. TIED ONTO CASING & PUMPED 80 SX CMT THEN 45 SX CMT WITH 200# HULLS. PRESSURED TO 1500#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
3918	3923		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

1/14/15CKM

District: 01

Signed Michael J. Maier  
(TECHNICIAN)

KCC WICHITA  
JAN 09 2015  
RECEIVED

RECEIVED  
JAN - 6 2015  
KCC DODGE CITY