

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-00092-00-00
Spot: NWSENE Sec/Twnshp/Rge: 25-32S-5E
3645 feet from S Section Line, 996 feet from E Section Line
Lease Name: STANDIFORD Well #: 1
County: COWLEY Total Vertical Depth: 3134 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3098 | | 100 SX |
| SURF | 8.625 | 100 | | 100 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2014 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed
Plugging
Method:

AS PER KCC RULES & REGS/ SAND BOTTOM W/5/ SXS, TBG @ 1000, CIRCULATE TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/28/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3050', DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE SET CIBP @ 1000', DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 350' - 351' (4 HOLES). RIH W/ TBG @ 970', QUALITY WELL SERVICE ESTABLISHED CIRCULATION. MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. RIH W/ 1" TBG ON BACKSIDE @ 210', QUALITY WELL MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. TOPPED WELL BACK TO SURFACE W/35 SXS 60/40 POZMIX 4% GEL. 10-29-14 TOPPED WELL BACK TO SURFACE W/ 25 SXS 60/40 POZMIX, CUT & BURIED WELL HEAD. TOTAL OF 205 SXS 60/40 POZMIX 4% GEL, QUALITY WELL SERVICE TICKET #6007.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3098 | 3134 | OH | |

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

Received
(TECHNICIAN)
KANSAS CORPORATION COMMISSION

JAN 02 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

1/2

1/14/15 CKM