

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20206-00-00
Spot: NWSENWSE Sec/Twnshp/Rge: 25-32S-5E
1672 feet from S Section Line, 1757 feet from E Section Line
Lease Name: STANDIFORD Well #: 3
County: COWLEY Total Vertical Depth: 3201 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3201		100 SX
SURF	8.625	212		190 SX

Well Type: SWD UIC Docket No: D15800.0 Date/Time to Plug: 10/27/2014 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RICHARD MCNENTYRE Company: QUALITLY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/28/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL @ 1150', DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 350'-351' (4 HOLES). RIH W/TBG @ 350', QUALITY WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING, RIH W/1" TBG ON BACKSIDE @ 110', QUALITY WELL MIXED & PUMPED 10 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. CEMENT CIRCUALTED. CUT & BURIED WELL HEAD. QUALITY WELL SERVICE TICKE T # 6008.

Perfs:

Top	Bot	Thru	Comments
1272	1277	CSG	

KCC WICHITA
JAN 06 2015
RECEIVED

Remarks:

Plugged through: TBG

1/14/15 ckm

District: 02

Signed Duane Krueger
(TECHNICIAN)
cc: uic ✓