

7-19

7
P

2-040546

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: D77-10012-00-02
15-0330

NE NE NW, SECTION 29 TOWNSHIP 31 RANGE 7W

OPERATOR LICENSE # 100 FEET FROM S SECTION LINE
FEET FROM E SECTION LINE

OPERATOR KCC *FEE FUND*
NAME & ADDRESS 202 West First, #304
Wichita, KS 67202

LEASE NAME: Tracey #1 OWWO
COUNTY: Harper
WELL TOTAL DEPTH: 4760'
CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 264'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: Clarke Corp.

ADDRESS: Medicine Lodge LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Steve Van Gieson
COMPANY NAME: KCC PHONE: _____
WERE: 4-1/2" @ 4915' - perms unknown - sand to 3900' & 4 sx
- 25 sx 1400' - 25 sx 1000' - circ cmt 300'-0' - casing
parted @ 130'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 18:30 DAY: 19 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Ran tubing & bit in hole to 130' - drilled out bridge
- got in 4-1/2" & ran to 4340' & spotted 35 sx cmt -
tub was laid down & perf gun was run in to 1400' where
two holes shot - cmt retainer was set at 1384' & 35 sx
cmt spotted - tub was laid down - perf could not get
back into 4-1/2" - tub was run back into 4-1/2" csq to
1000' & cmt circ back to surface.

REMARKS: B. J. Services #610903 common cmt.

I DID OBSERVE THIS PLUGGING.
STATE CORPORATION COMMISSION

RECEIVED
AUG 15 1990
8-15-90
Wichita, Kansas

Steve Van Gieson
Steve Van Gieson (AGENT)

DL