

7-16

8
R

2-040545

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-077-20,700-00-00

E/2 E/2 NW, SECTION 29 TOWNSHIP 31 RANGE 7W

OPERATOR LICENSE # 100 FEET FROM S SECTION LINE
FEET FROM E SECTION LINE

OPERATOR KCC *FEE FUND*
NAME & 202 West First, #304
ADDRESS Wichita, KS 67202

LEASE NAME: Tracey #2
COUNTY: Harper
WELL TOTAL DEPTH: 4757'
CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 294'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: Clarke Corp.

ADDRESS: Medicine Lodge LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Steve Van Gieson
COMPANY NAME: KCC PHONE: _____
WERE: 4-1/2" @ 4387' - perms unknown - pump 35 sx to 3955' -
25 sx 1400' - 25 sx 1000' - 125 sx 350'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 18:15 DAY: 16 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
A 35 sx cmt plug was pumped thru tub from 3955' - TOC
3731' - the 4-1/2" was recovered from 2015' - the tub
was run back in hole to 1417' where 25 sx of cmt was
spotted - tubing was pulled to 1008' where 25 sx cmt
was spotted - tub was pulled to 346' & cmt circ back to
surface.

REMARKS: B. J. Services #610825 common cmt.

I DID OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION
Steve Van Gieson (AGENT)

AUG 15 1990
8-15-90
Wichita, Kansas

FORM CP-2/3
REV. 3/90

Handwritten initials