

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00852-00-00
Spot: CNWNWNW Sec/Twnshp/Rge: 1-31S-9W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: RALL B Well Number: 1
County: HARPER Total Vertical Depth: 4510 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 SOUTH MAIN - SUITE 505
WICHITA, KS 67202

Conductor Pipe: Size feet: 3/46.58
Surface Casing: Size 8.625 feet: 203 85 SX CMT
Production: Size 4.5 feet: 4510 90 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/11/2002 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINYTRE Company: QUALITY WELL SERVICE Phone: (620) 793-2316

Proposed
Plugging
Method:

Perfs 4444'-4460'. Sand to 4390' and 4sxs of cement. 35sxs @ 1300', 35sxs @ 700'. Circulate cement 250'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 02/11/2002 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand from 4480'-4371', and capped w/4sxs of cement. The casing was recovered from 2676', and pulled to 1300', where 35sxs of cement was spotted. The casing was pulled to 700', where 35sxs of cement was spotted. The casing was pulled to 250', where cement was circulated to surface. The remaining casing was pulled and the cement was topped off.

RECEIVED
KCC DISTRICT #2

FEB 14 2002


WICHITA, KS

Remarks: ALLIED CEMENTING COMMON CEMENT

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE Feb 20-02

INV. NO. 2002061400