

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00869-00-00 Spot: C SWSESW
Sec: 13 Twnshp & Dir: 31 S Rng & Dir: 2 W
Feet: 330 frm N/S: S Feet: 3630 frm E/W: E
Lease/Unit Name: RYAN Well Number: 2
County: HARPER Total Vertical Depth: 4455 feet

Operator License No.: 5429
Operator Name: Hayes, Bryce F.
Address: West Highway 160
Attica, KS 67009

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 190
Production: Size 5.5 feet: 4455

*Rec'd
9-7-99*

144.79

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/01/1999 8:00 AM
Plug Co. License No.: 5105 Plug Co. Name: Clarke Corporation
Proposal Received from: Allan Vitral Company Name: Clarke Corp.
OpRepPhoneNo: (316) 886-5665

Were: KCC Reg


Plugging Proposal Received By: Steve VanGieson, KCC Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 09/07/1999 11:30 AM

Actual Plugging Report:

Open hole covered w/sand to 4270 & capped w/5sxs sand. 5 1/2" recvd. from 3000' & pulled from wellbore. Tubing to 1360'-35 sxs cem. spotted. Tubing to 765'-35 sxs cem. spotted. Tubing to 253'-cem. circulated to surf. Remaining tub. pulled & cem. topped off

INVOICED
DATE 11-5
INV. NO. 60802

Remarks: Allied Cementing 60/40 Poz 4% Gel SEE PA FILE FOR MORE INFORMATION
Anhydrite Plug: No Bottom Plug: No Dakota Plug: No
Plugged through:

I (did) ~~did not~~ observe this plugging. Signed  (TECHNICIAN)