

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00872-00-00
Spot: CNENESW Sec/Twnshp/Rge: 13-31S-9W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease/Unit Name: RYAN Well Number: 8
County: HARPER Total Vertical Depth: 4435 feet

Operator License No.: 5429 Conductor Pipe: Size 0 feet: 0 \$144.14
Op Name: HAYES, BRYCE F., DBA BRYCE F. OIL & Surface Casing: Size 8.625 feet: 192 150 SX CMT
Address: 1081 WEST HIGHWAY 160 PO BOX 108 Production: Size 5.5 feet: 4433 250 SX CMT
ATTICA, KS 67009 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/24/2000 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY Company: MIKE'S TESTING & SALVAGE Phone: (316) 886-0812

Proposed Plugging Method: Perfs 4350'. Sand to 4300'-5sxs, 35sxs-1250', 35sxs-800', circulate-250'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/24/2000 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were sanded back to 4300' and capped w/5sxs of cement. The casing was recovered from 2800' and pulled to 1250', where 35sxs of cement was spotted. Pulled casing to 800' spotted 35sxs of cement. Pulled casing to 250' and circulated cement.

RECEIVED
KCC DISTRICT #2

JUL 25 2002
7-25-02
WICHITA, KS

Remarks: ALLIED CEMENT 60/40, 4% GEL

Plugged through: CSG

District: 02

Signed _____


(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-5-02

INV. NO. 2003060158