

8-9-88

1 020170

API NUMBER 15-119-20,701-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW SE, SEC. 9, T 33 S, R 30 (W/E)

330 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Butler Well # 1-9

Operator: Murfin Drilling Company

County Meade 196.89

Name & Address 250 North Water, Suite 300

Well Total Depth 6058 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1514

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
AUG 16 1988

Abandoned Oil Well _____ Gas Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 9 Month: 8 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 6046' PBD 6003' Perfs at 5724-30'

1st plug sand back to 50' above perfs with 4 sx cement on top of sand with bailer,

2nd plug at 1540' with 50 sx cement,

3rd plug at 770' with 30 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All y Part _____ None _____

Operations Completed: Hour: 7 p.m. Day: 9 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 50' above perfs and dumped 4 sx cement on top of sand with bailer, TOC 5536'

2nd plug circulated jet mud in hole and pumped 50 sx cement at 1540',

3rd plug pumped 30 sx cement at 770',

4th plug pumped 10 sx cement at 40'-0'.

Remarks: Used common Class A cement by Halliburton. Recovered 3400' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Glenn R Barlow (TECHNICIAN)

DATE 8-16-88

INV. NO. 21866

Continued . . .

40 sacks cement, pulled to 40', pumped 10 sacks cement, pulled
shot joint.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1988

CONSERVATION DIVISION
Wichita, Kansas