

To: 1 020837 1-26
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,374-00-00
SE NE NE, SEC. 4, T 33 S, R 30 W
998 feet from ~~N~~ section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8222
Operator: Buttonwood Petroleum
Name & Address: 9 E. 4th St., Ste. 1000
Tulsa, OK 74103

Lease Name Richardson Well # 1
County Meade 148.04
Well Total Depth 4555 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1523

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Petrofield Services Corp. License Number 31330
Address 110 S. Hartford, Ste. 300, Tulsa, OK 74129

Company to plug at: Hour: 9 a.m. Day: 25 Month: 1 Year: 19 95
Plugging proposal received from Johnnie Brumley

(company name) Petrofield Services Corp. (phone) 405-222-9715

were: 5 1/2" at 4554' w/200 sx cement, TOC 2250', Perfs at 2714-24, 3238-42, 4513-17'
1st plug set CIBP at 4463' with 2 sx cement on top, 2nd plug set CIBP at 2664' with 2 sx cement on top, 3rd plug pull casing and run tubing to 1553' with 50 sx cement,
4th plug at 550' with 50 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:30 p.m. Day: 26 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4463' with 2 sx cement on top
2nd plug set CIBP at 2664' with 2 sx cement on top,
3rd plug ran tubing to 1553' and pumped 50 sx cement,
4th plug pumped 50 sx cement at 550',
5th plug filled 40' to -4' with cement.

Remarks: Used common cement by Petrofield Services. Recovered 2114' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 2-6-95
INV. NO. 42165
1-26

Signed Duane Rankin (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
FEB 01 1995
CONSERVATION DIVISION
WICHITA, KANSAS