

168R

1 110046

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,748-0000
NW NE, SEC. 2, T 33 S, R 30 W/2
4620 feet from S section line
1800 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3066
Operator: Wilbanks Operating, Inc.
Name & Address 1860 Lincoln St., Suite 1270
Denver, CO 80295

Lease Name Joyce George Well # 1-2
County Meade 200.53
Well Total Depth 6170 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1606

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mustang Drilling Inc. License Number 4813

Address P.O. Box 990, Great Bend, KS 67530

Company to plug at: Hour: 3:30 p.m. Day: 25 Month: 10 Year: 19 86

Plugging proposal received from Lee Berdsell

(company name) Mustang Drilling (phone) 316-792-6877

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2719' GL

1st plug at 30' below base of surface pipe with 50 sx cement

2nd plug at 660' with 25 sx cement

3rd plug at 40-0' with 10 sx cement

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:15 p.m. Day: 25 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT hole filled with mud between plugs

1st plug at 1640' with 50 sx cement

2nd plug at 660' with 25 sx cement

3rd plug solid bridge plug with 1 sx hulls at 40' with 10 sx cement

4th plug to circulate rathole with 15 sx cement.

OCT 31 1986

Remarks: Used 60/40 Pozmix 6% gel by Dowell Schlumberger.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 11-3-86

Signed James R. Day
(TECHNICIAN)

INV. NO. 15-286
10-25