

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10029-00-01
Spot: NESE Sec/Twnshp/Rge: 3-33S-30W
1991 feet from S Section Line, 669 feet from E Section Line
Lease/Unit Name: STEVENS (MORROW) UNIT Well Number: 309
County: MEADE Total Vertical Depth: 5880 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY STE. 350
HOUSTON, TX 77057

Conductor Pipe: Size feet: \$191.10
Surface Casing: Size 9.625 feet: 1609
Production: Size 5.5 feet: 5825
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 07/01/2001 3:00 PM

Plug Co. License No.: 5382 Plug Co. Name: CHEYENNE DRILLING, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: 1ST PLUG AT 2208' WITH 150 SX CMT. 2ND PLUG AT 1700' WITH 50 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE
Date/Time Plugging Completed: 07/01/2001 4:40 PM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2208'. 1ST PLUG AT 2208' WITH 150 SX CMT. 2ND PLUG AT 1700' WITH 50 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 20 2002

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED. RECOVERED 2208' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED

DATE Mar 20-02

INV. NO. 2002061550 MP

MAR 08 2002

FORM P-273