

1 110004

API NUMBER 15- OWWO

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW NE , SEC. 9 , T 33 S, R 30 W/R

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5421

Lease Name Jennings Well # 9-1

Operator: Sage Drilling Co., Inc.

County Meade 175.570

Name & Address 202 South St. Francis

Well Total Depth 5400 feet

Wichita, KS 67202

Conductor Pipe: Size 13 3/8 feet 631

Surface Casing: Size 8 5/8 feet 2689

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 10:00 am Day: 30 Month: August Year: 19 85

Plugging proposal received from Bob Sargent's

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5318' PBTD 5196' Perfs 5146-5151 Spot plugs through 4 1/2" casing with mud between plugs  
1st plug pump 2 sx hulls & 15 sx cement down casing with 9 ppg mud.

2nd plug pull free 4 1/2" casing and set plug with 4 1/2" casing at 2739' with 25 sx cement

3rd plug pump 50 sx cement in and out of 13 3/8" casing at 650'

4th plug pump 25 sx cement at 40' to surface

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:00 pm Day: 30 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 5885' with 15 sx cement, 2nd plug at 2740' with 25 sx cement, 3rd plug at 650' with 50 sx cement, 4th plug at 25 sx cement to surface.

RECEIVED STATE CORPORATION COMMISSION

SEP 6 1985

Remarks: Recovered 4370' 4 1/2" casing & 1000' 8 5/8" Used Common cement by Sargent's Casing Pulling Service (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE SEP 10 1985

Signed James R. Kahn (TECHNICIAN)

INV. NO. 9916