

1 031281
To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-16

API NUMBER 15- 119-20,905-0000
App. 120' W of
N/2 NW SE, SEC. 7, T. 33 S, R. 30
2310 feet from S section line
2100 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606
Operator: Murfin Drilling Co./Canyon Energy, Inc.
Name:
Address 250 N. Water, Ste. 300
Wichita, KS 67202

Lease Name Feiertag Well # 1-7
County Meade
Well Total Depth 5960 193.70 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1528

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 15 Month: 6 Year: 19 94

Plugging proposal received from Bill Wynn

(company name) Murfin Drilling Co. (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1560' with 50 sx cement, 2nd plug at 600' with 25 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:15 a.m. Day: 16 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,

2nd plug at 600' with 25 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED (if additional description is necessary, use BACK of this form)
XXXXX/ did not observe this plugging.

DATE 6-27-94
INV. NO. 40636

Signed Steve Durrant

RECEIVED
JUN 21 1994
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas