

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21739-00-01
Spot: NW Sec/Twnshp/Rge: 4-33S-32W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: MILHON Well Number: B-2
County: SEWARD Total Vertical Depth: 6080 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 5765 WITH 160 SX CMT
Surface Casing Size: 8.625 feet: 1626 WITH 410 SX CMT

\$19760

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2003 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Pumping Method: PUMP 2 SX HULLS AND 25 SX CMT FROM 4750 TO 4510. SHOOT OFF 5 1/2" CSG @ +/-2550. SPOT 50 SX CMT FROM 1650 TO 1525. SPOT 30 SX CMT FROM 650 TO 530. SPOT 15 SX CMT FROM 40 TO 4. CUT OFF AND CAP 8 5/8 CSG 4 BELOW GL.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/24/2003 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 5704'. PERFS AT 4598-4604'. CIBP @ 4750'. PORT COLLAR @ 2910' WITH 100 SX CMT. PUMP 200# HULLS WITH 25 SX CMT. DISPLACE WITH MUD & PRESSURE TO 500 PSIG. SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1650'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 650'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
OCT 14 2003
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENTS. RECOVERED 1925' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland *PERT#*
(TECHNICIAN)

INVOICED
DATE 10-14-03
INVOICE NO. 2004060607

[Signature]
FORM CP 2/9