

To: 1 031451 5-24
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-21,626-00-00
125' W & 130' N of
E/2 SE SW, SEC. 19, T. 33 S, R. 32 W X
790 feet from S section line
1525 feet from W X X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Harvey B Well # 2
County Seward 206.38
Well Total Depth 6350 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1578

Abandoned Oil Well Gas Well Input Well SMD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 7 p.m. Day: 24 Month: 5 Year: 19 97

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3100' with 100 sx cement, 2nd plug at 1590' with 50 sx cement,

3rd plug at 630' with 25 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 p.m. Day: 24 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 3100' with 100 sx cement,

2nd plug at 1590' with 50 sx cement,

3rd plug at 630' with 25 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 05 1997

INV. NO. 48219

Signed Steve Durrant (TECHNICIAN)

RECEIVED
KANSAS CORP COM
JUN 11 1997
6-2-97
A 3:37