

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21602-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 21-33S-32W  
100 feet from N Section Line, 990 feet from W Section Line  
Lease/Unit Name: COLBURN Well Number: 3-21  
County: SEWARD Total Vertical Depth: 3150 feet

Operator License No.: 5263 Conductor Pipe Size: 30 feet: 70 WITH 7.5 YDS CMT  
Op Name: MIDWESTERN EXPLORATION COMPA Production Casing Size: 4.5 feet: 2982 WITH 200 SX CMT  
Address: 3500 S BOULEVARD - SUITE 2B Surface Casing Size: 8.625 feet: 572 WITH 120 SX CMT  
EDMOND, OK 73013

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/20/2003 9:00 AM  
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.  
Proposal Rcvd. from: BUTCH DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 2380' WITH 2 SX CMT. LOAD HOLE WITH MUD. 40 SX STUB PLUG AT CUTOFF. 50 SX CMT AT 1400'. 50 SX CMT AT 600'. 20 SX CMT AT 40'.  
# 10238

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/20/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2540'. PERFS AT 2426-32, 2458-73, 2496-2512'. CIBP @ 2380' WITH 2 SX CMT ON TOP. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE TO 1370'. TRIED TO CIRCULATE HOLE. PRESSURED TO 500 PSIG. DID NOT CIRCULATE. PIPE STUCK AT 1100'. WORKED LOOSE & PULLED OUT OF HOLE TO 1070'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 15 SX CMT TO SURFACE.


RECEIVED

OCT 30 2003  
10-30-03  
KCC WICHITA

Remarks: USED CLASS A CMT BY JERRY DUNKIN, INC. RECOVERED 1431' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED  
DATE 10-30-03  
NO. 2004060699

Form CR-03