

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21344-00-01  
Spot: CNESW Sec/Twnshp/Rge: 33-33S-31W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: HARRIS Well Number: 1  
County: SEWARD Total Vertical Depth: 6080 feet

Operator License No.: 5652  
Op Name: MUSTANG OIL AND GAS CORP.  
Address: 100 S. MAIN ST. #300  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 1530 WITH 700 SX CMT  
Production: Size 5.5 feet: 6061 WITH 105 SX CMT  
Liner: Size \_\_\_\_\_ feet: \$197.60

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2001 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: JERRY GREEN Company: CASTLE RESOURCES Phone: \_\_\_\_\_

Proposed Plugging Method: 1ST PLUG CIBP @ 5700'. SQUEEZE PERFS WITH 100 SX CMT. 2ND PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/27/2001 5:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5700'. DV @ 3446' WITH 150 SX CMT. PERFS AT 5758-5764, 2778-84, 3114-18'. 1ST PLUG SET CIBP @ 5700'. 2ND PLUG SQUEEZE PERFS AT 2778-3118' WITH 100 SX CMT (MAXIMUM PSI 100#). DISPLACE CMT TO 2400' WITH 58 BBLs WATER. 3RD PLUG PULL OUT OF HOLE TO 1530'. PUMP 15 SX GEL & 50 SX CMT. 4TH PLUG PULL OUT OF HOLE TO 660' PUMP 50 SX CMT. 5TH PLUG PULL OUT OF HOLE TO 40' PUMP 10 SX CMT.

RECEIVED  
AUG - 7 2001  
8-7-01  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 2000' OF 5 1/2" CASING

Plugged through: CSG

District: 01

Signed

Jim Holland PART II  
(TECHNICIAN)

AUG 03 2001

Form CP-100

*MP*

*[Signature]*

INVOICED  
DATE 8-7-01  
9002060196