

To: 1 060129 4-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-175-10071-00-00
API NUMBER 15- Drill Completion Date 11/9/61

C NW SE, SEC. 35, T 33 S, R 31 W EX
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name & Address: Rt. 1, Box 56
Great Bend, KS 67530

Lease Name Hays Well # 2
County Seward
Well Total Depth 5926 192.59 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1244

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pipe Recovery, Inc. License Number 30752
Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 4 Year: 19 92

Plugging proposal received from Rick Davis
(company name) Pipe Recovery, Inc. (phone) 316-793-3922

were: 5 1/2" at 5908' w/200 sx cement, PBD 5890', Perfs at 4431-40'
1st plug sand back to 4380' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 16 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 4-27-92
INV. NO. 35057

Signed Carl M... (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
4-20-92
APR 20 1992