

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe & Supply

Complete Address: Box 960, Bristow, Oklahoma

Lease Name: Leslie Well No. 1

Location: 0 SW NE Sec. 3 Twp. 33 Rge. 30 (E) (W)

County: Meade Total Depth 5760' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

13 3/8" to 642' circulated w/ cement. 8 5/8" to 2674' cemented.


5 1/2" to 5745' cemented. Top perforations ~~5660'~~ <sup>5660'</sup>

Plug bottom w/ 20 sacks cement. Top of cement 5550'

Mud 5550' to 650' Spot 50 sacks cement 650' to 550'

Mud 550' to 40' Plug, Hulls & 20 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent