

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAY 1 - 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mc Adams has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.Operator's full Name: McAdams Pipe & Supply Co.Complete Address: Box 960, Bristow, OklahomaLease Name: Kelly Well No. 1Location: C NE SW Sec. 3 Twp. 33 Rge. 30 (E) (W)County: Meade Total Depth 5842' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Sargent was instructed to plug the well as follows:

13 3/8" to 651' circulated w/ cement. 8 5/8" to 2675' cemented.

5 1/2" to 5811' cemented. Top perforations 5676'

Plug bottom w/ 20 sacks cement. Top of cement 5550'

Mud 5550' to 900' Spot 50 sacks cement 900' to 800'

Mud 800' to 40' Bridge & 20 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent