

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe & Supply Co.

Complete Address: Box 960, Bristow, Oklahoma

Lease Name: Leslie "A" Well No. 1

Location: C SE NW Sec. 3 Twp. 33 Rge. 30 XX (E) (W)

County: Meade Total Depth 5820' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

13 3/8" to 672' circulated w/ cement. 8 5/8" to 2660' cemented.


5 1/2" to 5800' cemented. Top perforations 5659'

Plug bottom w/ 20 sacks cement. Top of cement 5550'

Mud 5550' to 600' Spot 50 sacks cement 600' to 500'

Mud 500' to 40' Plug, Halls & 20 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent