

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Shamrock has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Diamond Shamrock Corporation

Complete Address: Box 631, Amarillo, Texas

Lease Name: Pauline V. Hulburt Well No. 1

Location: NE NE NE Sec. 5 Twp. 33 Rge. 30 (E) (W)

County: Meade Total Depth 5649' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

9 5/8" to 2676' circulated w/ cement. 7" to 5647' cemented.

Top perforations 5581' Plug bottom w/ 25 sacks cement.

Top of cement 5400' Mud 5400' to 900'

Spot 40 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Green
Conservation Division Agent