



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Smith of James F. Smith has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: James F. Smith

Complete Address: 1705 Avendale, Box 10005, Amarillo, Texas

Lease Name: Holmes Well No. # 1

Location: C NE SW Sec. 10 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 6300' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Smith was instructed to plug the well as follows:

- 8 5/8"-2 1/4" 1' Cir. w/cem. 4 1/2"-6298' Cemented. Top Perforations - 6215'
- Plug bottom w/ 40 sax. cement. 6300' to 5700' Mud 5700' to 700'
- Plug, 35 sax. cement 700' to 600' Mud 600' to 40'
- Plug, 15 sax. cement 40' to surface.

Very truly yours,

*[Signature]*  
 Conservation Division Agent