



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202  
5-31-82

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
15-175-20, 626-00-00

Dear Sir:

Mr. Jim Barlow of Anadarko Production Co. has this date requested permission to plug the following described well:

Operator's Full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal Kansas 67901

Lease Name: Milhon Well No. A1

Location: C-SW-NE Sec. 9 Twp. 33 Rge. 32 (E) (W)

County: Seward Total Depth: 6250'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Barlow was instructed to plug the well as follows:

They cement circulated 1622' of 8 5/8" surface casing, 1st plug at 2450' with 40 bbls of cement, 2nd plug at 1680' with 40 bbls of cement, 3rd plug at 810' with 35 bbls of cement, 4th plug on solid bridge at 40' to 0' with 10 bbls of cement, then circulated 10 bbls of cement in rat hole & 10 bbls in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co. Mr. Melvin Plough gave these orders.  
Very truly yours,

RECEIVED  
STATE CORP.  
JUN - 8 1982  
6-8-82  
CONSERVATION DIVISION  
Wichita, Kansas

Paul A. Luttich  
Conservation Division Agent