

15-175-10029-00-00

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 1 1963
 10-1-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Minney of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Minney guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 6 Liberal, Kansas

Lease Name: Salley Well No. E-1

Location: C NE SW Sec. 20 Twp. 33 Rge. 32 (E) (W)

County Seward Total Depth 6292' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Minney was instructed to plug the well as follows:

- 8 5/8" - 1425' Circulated w/cement.
- Mud 6292' to 2750' Spotted 25 Sax.cement 2750' to 2669'
- Mud 2669' to 2450' Spotted 25 Sax.cement 2450' to 2369'
- Mud 2369' to 700' Spotted 35 Sax.cement 700' to 592'
- Mud 592' to 40' Plug, Hulls, 15 Sax.cement 40' to 0

Very truly yours,

Hugh Scott
 Conservation Division Agent