

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Luck of Thomas & Brewer has this date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Box 1177, Liberal, Kansas

Lease Name: Eaton Well No. 1

Location: NE SE Sec. 27 Twp. 33 Rge. 31 (W)

County Seward Total Depth 6100' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8" to 1466' circulated w/ cement. 4 1/2" to 3410' cemented

Plug back T.D. 3380' TOP of perforations 3072'

Plug bottom w/15 sacks cement, Top of cement 2900'

Mud 2900' to 700' Spotted 40 sacks cement 700' to 600'

Mud 600' to 40' Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Edgar J. Jones
Conservation Division Agent