

State of Kansas



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 22 1962
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 20 October, 1962, authorized

The following plugging operation:

Operator's full Name: Cabot Corporation

Complete Address: Box 1101 Pampa, Texas

Lease Name: Eaton-Griffith Well No. # 1

Location: C SW NE 1980' FN&EL Sec. 33 Twp. 33S Rge. 31 (E)(W)

County Seward Total Depth: 6330'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

8 5/8" 2417' Cemented w/1000 sax.cement

Mud 6330' to 6116' Cement 6116' to 6025' 25 sax.

Mud 6025' to 4559' Cement 4559' to 4460' 25 sax.

Mud 4460' to 818' Cement 818' to 700' 35 sax.

Mud 700' to 48.6' Cement 48.6' to 4' below surface.

Cup pipe off 4' below surface. Weld on cap.
Very truly yours,

[Handwritten Signature]

