



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 14 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Mc Allister of Rainbow Exploration Inc. has this date requested permission to plug the following described well:

Mr. Mc Allister guarantees payment of the plugging fee.

Operator's full Name: Rainbow Exploration Inc.

Complete Address: 1001 Union Center. Wichita, Kansas

Lease Name: Eaton-Griffith Well No. #1

Location: SW NE Sec. 33 Twp. 33 Rge. 31 (E) (W)

County Seward Total Depth 4527' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mc Allister was instructed to plug the well as follows:

8 5/8" 2420' Circulated w/cement. 4 1/2" 4518' Cemented.

Mud 4527' to 2605' 25 sax.cement 2605' to 2500'

Mud 2500' to 700' Plug, 35 sax.cement 700' to 600'

Mud 600' to 40' Plug, 15 sax.cement 40' to surface.

Very truly yours,

[Handwritten Signature]
 Conservation Division Agent