



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 1 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Myers of Panhandle Development Co. has this date requested permission to plug the following described well:

Mr. Myers guarantees payment of the plugging fee.

Operator's full Name: Panhandle Development Co. Inc.

Complete Address: 801 Union Center. Wichita, Kansas

Lease Name: Higgins Well No. # 3

Location: C NW NW Sec. 35 Twp. 33S Rge. (E) (W) 31

County Seward Total Depth 4506' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Myers was instructed to plug the well as follows:

8 5/8" - 1252' Circulated w/cement.

Mud 4506' to 700' Spotted 35 Sax. cement 700' to 600'

Mud 600' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

*[Signature]*  
 Conservation Division Agent