

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217
RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Meyer of Abercrombie has this

date requested permission to plug the following described well:

Mr. Meyer guarantees payment of the plugging fee.Operator's full Name: A.L. Abercrombie Inc.Complete Address: 801 Union Center Bldg., Wichita, KansasLease Name: Higgins Well No. 2Location: SE NW Sec. 35 Twp. 33 Rge. 31 (E) (W)County: Seward Total Depth 5970' Oil Well Gas Well X Input Well SWD Well D & A Lost Hole Mr. Meyer was instructed to plug the well as follows:8 5/8" to 1254' circulated w/ cement. 5 1/2" to 4555' cemented.Top perforations 4309' Plug bottom w/ 20 sacks cement.Top of cement 4200' Mud 4200' to 800'Spot 35 sacks cement 800' to 700' Mud 700' to 45'Plug, Halls 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent